

These notes based on discussions from today's walkthrough represent an addenda issued during the time of the request for proposal.

The individual projects listed on this RFP may be awarded separately. Vendors may send a proposal for any or all of the projects included within the RFP.

For the WAN installation: Fiber must be buried on our campus. No aerial installations will be permitted.

For Data Center Switches: General Specifications will include System Switching Capacity of 14 Tbps. Also all GBICS will be SR (no LRM). Revised minimum port requirements will be 12 SR GBICS for Switch ONE and 23 SR GBICS for Switch 2.

For Data Center Switches, Network Switches at Hahira Elementary and Dewar Elementary, and for Network Modules for Pine Grove Middle, configuration and engineering is to include installation of the switches and components.